ALL DIMENSIONS SHOWN ARE IN METRES AND/OR MILLIMETRES UNLESS OTHERWISE NOTED.


SHELTER No.	SHELTER SIZE	MIN. CONC. BASE SIZE	PASSENGER CAPACITY	ROOF TYPE	No. OF BENCHES	POWER DOOR OPENER	REMARKS
1A	2438×7658	2838×10400	48	DOME	2	YES	PROVIDE STD H/C RAMP (1:15 MAX. SLOPE) FOR BOTH DOORS (2)
1B	2438x7658	2838×10400	48	PEAKED	2	YES	PROVIDE STD H/C RAMP (1:15 MAX. SLOPE) FOR BOTH DOORS (2)



- 1. GIVEN DIMENSIONS ARE OUTSIDE POST TO OUTSIDE POST. THE SECOND GIVEN DIMENSION (7658mm) IS APPROXIMATE, ACTUAL DIMENSION TO BE DETERMINED BY SHELTER MANUFACTURER AS TO MEET GLASS SIZE REQUIREMENT (1220X1071 PANELS). SEE DWG. (RBS-1B-002) AND SPECIFICATIONS.
- 2. EXTEND SLAB AS REQUIRED TO SUIT SITE CONDITIONS AND PROVIDE 1:15 SLOPE. BLEND RAMP INTO EXISTING PLATFORM CROSS SLOPE.
- 3. PROVIDE BARRIER FREE POWER DOOR OPENER SYSTEM TO SHELTER DOOR CLOSEST TO MINI PLATFORM ONLY. INCL. POWER DOOR OPENER UNITS, STL POSTS, POST/JAMB MOUNTED PUSH PLATES AND BOXES, LOCKING KEY SWITCHES, ETC. AS SPECIFIED AND SHOWN ON DRAWINGS.

		PLAT	FORM SHELTER
INDEX No.	DESCRIPTION	ENGINEERED	2438mm SHELTER DRAWING No.
1	CORNER FRAME DETAIL: ALL CONNECTIONS, CONNECTIONS WITH GLAZING FRAMES AND ELECTRICAL JUNCTION BOX.	YES (RBS-1B-001/RBS-1B-002
2	MIDDLE FRAME DETAIL: ALL CONNECTIONS, CONNECTIONS WITH GLAZING FRAMES, HORIZONTAL MULLION, AND WIND SKIRT.	YES	RBS-1B-001/RBS-1B-002
3	END FRAME DETAIL: ALL CONNECTIONS, CONNECTIONS WITH GLAZING FRAMES, DOOR SAFETY BAR, HORIZONTAL MULLION, ELECTRICAL JUCTION BOX, AND DOOR STOP.	YES	RBS-1B-001/RBS-1B-002
4	HORIZONTAL MULLION DETAIL: SHAPES OF EXTRUSIONS, CUT SIZE, GASKETING, NOTCHES, AND CONNECTION DETAILS.	YES	RBS-1B-001/RBS-1B-002
5	WIND SKIRT DETAIL: MATERIAL (ALUMINUM), SHAPE, CUT SIZE, CONNECTION DETAILS.	YES	RBS-1B-001/RBS-1B-002
6	BASE DETAIL: BASE PLATE DETAIL, SLEEVE DETAIL (INCL. PROVISION FOR FUTURE HEATER OUTLET), ALL SIZES, FASTENER DETAILS.	YES	RBS-1B-001/RBS-1B-002
7	ROOF CROSS SECTION: DETAILS OF EXTRUSIONS, GASKETS, AND FASTENERS. ALL CONNECTIONS.	YES	RBS-1B-001/RBS-1B-002
8	ROOF CROSS SECTION: SPACING OF RIBS, BOTTOM CAP DETAILS, RIB RADIUS, AND END ANGLE DETAIL, ALL GASKETS, SEALANT. ALL CONNECTIONS.	YES	RBS-1B-001/RBS-1B-002
9	DOOR DETAIL: TYPE OF DOORS, FRAME DETAILS, DOOR CLOSER, LOCK, HINGE, PULL AND PUSH, DOOR STOP/HOLD OPEN DETAILS.	YES	RBS-1B-001,RBS-1B-002, RBS-1B-003
10	EASY ACCESS BENCH DETAIL: COMPONENT SIZES AND DETAILS, FASTENERS, CONNECTION DETAILS, CONNECTIONS TO SHELTER BASE.	YES	RBS-1B-005
11	ELECTRICAL JUNCTION BOX: COMPONENT SIZES AND DETAILS, FASTENERS, CONNECTION DETAILS. SHOWING RELATION TO ELECTRICAL.	YES	RBS-1B-007
12	DOOR LOUVRE: SHOWING CUT SIZE, LAYOUT OF PERFORATIONS, METHOD OF PERFORATION.	YES	> RBS-1B-003
13	BARRIER FREE POWER DOOR OPENER: POWER DOOR OPENER DETAILS, STEEL POST DETAILS, POST/JAMB MOUNTED PUSH PLATES AND BOXES, BARRIER FREE SIGN, LOCKING KEY SWITCH, MOUNTING HEIGHTS, WIRING DIAGRAM AND DETAILS, ETC.	YES	> RBS-1B-004
14	GENERAL ASSEMBLIES: SHOWING ASSEMBLIES/CONNECTIONS NOT SHOWN IN OTHER SHOP DRAWINGS, MOUNTING DETAILS AND MOUNTING HEIGHTS OF ALL EQUIPMENT/FIXTURES. FINISH SCHEDULE.	YES	RBS-1B-002
15	SNOW GUARD	YES	RBS-1B-002

NOTE: THIS DRAWING IS PROVIDED FOR INSTRUCTIONAL DESIGN PURPOSES ONLY BASED ON METROLINX GO TRANSIT DESIGN GUIDELINES AND REQUIREMENTS. THE CONSULTANT SHALL VERIFY FOR LOCAL CODE COMPLIANCE, EXISTING SITE CONDITIONS AND INTER DISCIPLINARY DRAWING COORDINATION. ALL DIMENSIONS AND SPECIFICATIONS SHOULD BE VERIFIED BY CONSULTANT AND/OR CONTRACTOR BEFORE ACTUAL CONSTRUCTION BEGINS.



FRONT ELEVATION END ELEVATION

TYPE 1B - SIDE ENTRANCES - PEAKED ROOF

$\overline{2}$	SCHEDULE	OF	REQUIRED	SHOP	DRAWINGS
RBS-1B-006/	SCALE: N.T.S.				

	REFERENCE DRAWINGS			ISSUE			REVISIONS	DRAWN BY:	DESIGNED BY:
								G.R 07/09/22	GO TRANSIT
					5	JUN 2014	DRAWING NUMBER REVISION	CHECKED BY:	APPROVED BY:
					4	DEC 2013	DISCLAIMER NOTE	D.S.P	, , , , , , , , , , , , , , , , , , , ,
					3	SEPT 2013	RAMP AND HANDRAIL REVISION		
					2	AUG 2013	COLOUR REVISION	SCALE: NONE	FULL SIZE ONLY
					1	JULY 2012	NOMENCLATURE REVISION		
DWG NO.	TITLE	REV.	DATE	ISSUED FOR	REV.	DATE			

		0.01.175

A Division of Metrolinx

NEW SHELTERS PEAKED ROOF SHELTER SCHEDULE

METROLINX PROJECT NO.

DWG. NO.

CONTRACT NO. REV. SHEET RBS-1B-006